



IT IS THE CONTRACTORS RESPONSIBILITY TO CHECK ALL SETTING OUT DIMENSIONS AND REPORT ANY DISCREPANCY TO THE STRUCTURAL ENGINEER IMMEDIATELY.



- NOTES.**
-
1. ALL MATERIALS AND WORKMANSHIP TO BE STRICTLY IN ACCORDANCE WITH THE SPECIFICATION AND ALL RELEVANT BRITISH STANDARDS.
 2. ABBREVIATIONS
B-BOTTOM T-TOP
EF-EACH FACE
 3. ALL REINFORCEMENT TO BE HIGH YIELD TYPE B500A, B500B OR B500C RIBBED BARS TO BS4449:2005.
 4. BENDING AND SCHEDULING OF REINFORCEMENT TO BE IN ACCORDANCE WITH BS 8666 : 2005
 5. CONCRETE COVER TO ALL REINFORCEMENT TO BE 40mm UNLESS NOTED OTHERWISE.
 6. REINFORCEMENT DETAILED ON THIS DRAWING IS SCHEDULED ON BAR LIST No 501180C-015-01
 7. THIS DRAWING TO BE READ IN CONJUNCTION WITH DRAWING 501180C-20-018 & ALL OTHER SEJC DETAILS & RELEVANT ARCHITECTS DRAWINGS.
 8. CONCRETE FOR RETAINING WALLS TO BE C40. REFER TO SEJC STANDARD CONCRETE SPEC..

MK	REVISIONS		BY	DATE
				CHK

STATUS:—

AS-BUILT

DRAWN BY JL _____ DATE APRIL 2008 _____
 CHECKED BY CMW _____ DATE APRIL 2008 _____
 PROJECT ENGINEER _____ DATE _____

CLIENT.

CTP	S ^t JAMES
-----	----------------------

ARCHITECT.
FaulknerBrowns

CONTRACT
WAKEFIELD WATERFRONT
BUILDING 20



SEJC Consulting Engineers
Consulting Structural & Civil Engineers

Sanderson House, Station Road, Horsforth, Leeds LS18 5NT
Telephone 0113 2590080 Fax 0113 2588640

DRAWING TITLE

EXTERNAL RETAINING WALL
DETAILS (SHEET 1 OF 2)

SCALES AS SHOWN @A1

CONTRACT No	DRG No			
501180C	20-015			