

- ## NOTES
- STEELWORK NOTES:**
1. ALL STEELWORK TO BE S275 TO EN10025 UNLESS NOTED OTHERWISE
 2. STEELWORK TO BE DESIGNED, FABRICATED AND ERECTED IN ACCORDANCE WITH SEAC CONSULTING ENGINEERS SPECIFICATION
 3. THIS DRAWING TO BE SHOT IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS AND SEAC CONSULTING ENGINEERS DRAWINGS
 4. WITH THE EXCEPTION OF COLO ROLLED SECTIONS, ALL STEELWORK TO BE DRIFT BLENDED TO SWEDISH STANDARD AND PAINTED ONE COAT HIGH BUILD ZINC PHOSPHATE PRIMER TO 0.17 OF 75 MICRONS, ALL DAMAGED AREAS OF COATING TO BE CLEANED AND TOUCH-UP PAINTED AFTER ERECTION
 5. STEELWORK IN MASONRY CAVITIES TO BE GIVEN 2 COATS OF BITUMEN BASED PAINT (BY THE MAIN CONTRACTOR)
 6. ALL CONNECTIONS TO BE GIVEN A MINIMUM OF ZINC M20 BOLTS GRADE 8.8
 7. ALL BASEPLATES TO HAVE MINIMUM 4NO. HOLDING DOWN BOLTS
 8. THE STEELWORK CONTRACTOR SHALL INCLUDE FOR ALL TEMPORARY OR PERMANENT BRACES AND ALL NECESSARY TEMPORARY PROPS AND SUPPORTS TO ENSURE TOTAL STABILITY TO THE STRUCTURE AT ALL TIMES
 9. THE STEELWORK FABRICATOR WILL BE RESPONSIBLE FOR TANKING ALL NECESSARY SITE DIMENSIONS FOR FABRICATION PURPOSES.
 10. THE STEELWORK FABRICATOR WILL BE RESPONSIBLE FOR THE DESIGN OF ALL STEELWORK CONNECTIONS, ALL DRAWINGS AND CALCULATIONS SHALL BE SUBMITTED TO THE STRUCTURAL ENGINEER FOR COMMENTS PRIOR TO FABRICATION OF THE STEELWORK
 11. STEELWORK BELOW GROUND FLOOR LEVEL TO BE CLEANED TO SPECIFICATION, UNPAINTED AND CASED IN MINIMUM 100MM THICK CONCRETE UNO
 12. FOR POSITIONS AND DETAILS OF HOLDING DOWN BOLTS REFER TO THE STEELWORK CONTRACTORS DRAWINGS
 13. THE STEELWORK CONTRACTOR WILL DESIGN, SUPPLY, FABRICATE AND ERECT IN ACCORDANCE WITH THE CURRENT CODES OF PRACTICE
 14. INCLUDE FOR ALL TEMPORARY AND PERMANENT BRACES AND ALL NECESSARY PROPS AND SUPPORTS TO ENSURE TOTAL STABILITY TO THE STRUCTURE AT ALL TIMES

[illegible]

STATUS:—
AS BUILT

DRAWN BY _ S H.	DATE 26/2/07
CHECKED BY _ J L	DATE 26/2/07
PROJECT ENGINEER	DATE

CLIENT.


CTP	St JAMES
-----	----------

ARCHITECT.

FaulknerBrowns

CONTRACT

WAKEFIELD WATERFRONT
PHASE 1,
BUILDING 20



SEJC Consulting Engineers
Consulting Structural & Civil Engineers

Sanderson House, Station Road, Horsforth, Leeds LS18 5NT
Telephone 0113 2590090 Fax 0113 2588640

DRAWING TITLE

STEELWORK DETAILS TO
ENTRANCE LOBBY

SCALES 1:50,1:25 (@A1)

CONTRACT No 501180C	DRG No 20-206
------------------------	------------------