

NOTES

STEELWORK NOTES:

1. ALL STEELWORK TO BE S275 TO BS EN10025 UNLESS NOTED OTHERWISE
2. STEELWORK TO BE DESIGNED, FABRICATED AND ERECTED IN ACCORDANCE WITH SEJC CONSULTING ENGINEERS' SPECIFICATION
3. DRAWINGS TO BE SUBMITTED TO THE STRUCTURAL ENGINEER BY ALL RELEVANT ARCHITECTS AND SEJC CONSULTING ENGINEERS DRAWINGS
4. WITH THE EXCEPTION OF COLD ROLLED SECTIONS, ALL STEELWORK TO BE SHOT BLASTED TO SWEDISH STANDARD S4. 2/5 AND PAINTED ONE COAT HIGH BUILD ZINC PHOSPHATE PRIMER TO D.F.T. OF 75 MICRONS, ALL DAMAGED AREAS OF COATING TO BE CLEANED AND TOUCH-UP PAINTED AFTER THE WORK HAS BEEN NOTED OTHERWISE.
5. STEELWORK IN MASONRY CAVITIES TO BE GIVEN 2 COATS OF BITUMEN PAINTED BY THE MAIN CONTRACTOR AFTER THE WORK HAS BEEN NOTED OTHERWISE.
6. ALL CONNECTIONS TO HAVE A MINIMUM OF 2 No M20 BOLTS GRADE 8.8
7. ALL BASEPLATES TO HAVE MINIMUM 4 No. HOLDING DOWN BOLTS
8. THE STEELWORK CONTRACTOR SHALL INCLUDE FOR ALL TEMPORARY AND PERMANENT BRACINGS AND ALL NECESSARY TEMPORARY PROPS AND SUPPORTS TO ENSURE TOTAL STABILITY TO THE STRUCTURE AT ALL TIMES
9. THE STEELWORK FABRICATOR WILL BE RESPONSIBLE FOR TAKING ALL NECESSARY SIZE DIMENSIONS FOR FABRICATION PURPOSES
10. THE STEELWORK FABRICATOR WILL BE RESPONSIBLE FOR THE DESIGN OF ALL STEELWORK CONNECTIONS, ALL DRAWINGS AND CALCULATIONS SHALL BE SUBMITTED TO THE STRUCTURAL ENGINEER FOR COMMENTS PRIOR TO FABRICATION OF THE STEELWORK
11. STEELWORK BELOW GROUND FLOOR LEVEL TO BE CLEANED TO SPECIFICATION, UNPAINTED AND CASED IN MINIMUM 100mm THICK CONCRETE
12. FOR POSITIONS AND DETAILS OF HOLDING DOWN BOLTS REFER TO THE STEELWORK CONTRACTORS DRAWINGS
13. THE STEELWORK CONTRACTOR WILL DESIGN, SUPPLY, FABRICATE AND ERECT IN ACCORDANCE WITH THE CURRENT CODES OF PRACTICE
14. INCLUDE FOR ALL TEMPORARY AND PERMANENT BRACINGS AND ALL NECESSARY PROPS AND SUPPORTS TO ENSURE TOTAL STABILITY TO THE STRUCTURE AT ALL TIMES

MK	REVISIONS		BY	DATE	CHK

STATUS:—
AS BUILT

DRAWN BY SH. DATE JAN.'08
CHECKED BY DATE
PROJECT ENGINEER DATE

CLIENT.


CTP	S ^t JAMES
-----	----------------------

ARCHITECT.

FaulknerBrowns

CONTRACT

WAKEFIELD WATERFRONT
PHASE 1,
BUILDING 20



SEJC Consulting Engineers
Consulting Structural & Civil Engineers

Sanderson House, Station Road, Horsforth, Leeds LS18 5NT
Telephone 0113 2590090 Fax 0113 2586640

DRAWING TITLE

TRIMMER STEEL & ROOF DECK FIXING DETAILS

SCALES	AS SHOWN	(@A1)
--------	----------	-------

CONTRACT No	DRG No			
501180C	20-218			