



NOTES			
CONCRETE NOTES			
1. ALL MATERIALS AND WORKMANSHIP TO COMPLY WITH S.E.J.C. CONSULTING ENGINEERS STANDARD SPECIFICATION FOR REINFORCED CONCRETE AND ALL RELEVANT BRITISH STANDARDS.			
2. THIS DRAWING TO BE READ IN CONJUNCTION WITH ALL RELEVANT ARCHITECTS AND S.E.J.C. CONSULTING ENGINEERS DRAWINGS.			
3. ALL REINFT IS LISTED ON BAR SCHEDULE No's 501180/301 - 01 to 03 INCLUSIVE.			
4. 40mm. MINIMUM COVER TO ALL REINFORCEMENT			
5. 'T' DENOTES.....TOP 'B' DENOTES.....BOTTOM 'EF' DENOTES.....EACH FACE			
MK REVISIONS			
BY			
DATE			
CHK			
STATUS:- AS BUILT			
DRAWN BY _ _SH_			
DATE _ _FEB_'07			
CHECKED BY _ _AA_			
DATE _ _FEB_'07			
PROJECT ENGINEER _ _			
DATE _ _			
CLIENT			
CTP S' JAMES			
ARCHITECT			
FaulknerBrown			
CONTRACT			
WAKEFIELD WATERFRONT PHASE 1, BUILDING 20			
DRAWING TITLE			
RC. DETAILS OF GROUND BEAMS AT LOWER BASEMENT LEVEL (SSL. 20.400)			
SCALES 1:50,1:25,1:100 (@A1)			
CONTRACT No 501180C			
DRG No 20-301			