



SECTION 4-4.

NOTES

1. ALL MATERIALS AND WORKMANSHIP TO BE STRICTLY IN ACCORDANCE WITH THE SPECIFICATION AND ALL RELEVANT BRITISH STANDARDS.
2. ABBREVIATIONS
B-BOTTOM T-TOP
EF-EACH FACE NF-NEAR FACE FF-FAR FACE
AB-ALTERNATE BARS
ABS-ALTERNATE BARS STAGGERED
ABR-ALTERNATE BARS REVERSED
3. ALL REINFORCEMENT TO BE HIGH YIELD TYPE B500A, B500B OR B500C RIBBED BARS TO BS4449:2005.
4. BENDING AND SCHEDULING OF REINFORCEMENT TO BE IN ACCORDANCE WITH BS 8666 : 2005
5. CONCRETE COVER TO ALL REINFORCEMENT TO BE 40mm UNLESS NOTED OTHERWISE.
6. REINFORCEMENT DETAILED ON THIS DRAWING IS SCHEDULED ON BAR LISTS Nos 308/1 & 2.
7. THIS DRAWING TO BE READ IN CONJUNCTION WITH RELEVANT ARCHITECTS DRAWINGS & SEJC DETAILS.
8. ALL KICKERS TO BE 150 HIGH.

MK	REVISIONS	BY	DATE	CH'K
----	-----------	----	------	------

STATUS:-
AS BUILT

DRAWN BY _ _ BT. DATE _ _ APRIL '07
CHECKED BY _ _ DATE _ _
PROJECT ENGINEER _ _ DATE _ _

CLIENT.

CTP	St JAMES
-----	----------

ARCHITECT.

FaulknerBrowns

CONTRACT
WAKEFIELD WATERFRONT
PHASE 1,
BUILDING 20



SEJC Consulting Engineers
Consulting Structural & Civil Engineers

Sanderson House, Station Road, Horsforth, Leeds LS18 5NT
Telephone 0113 2590090 Fax 0113 2586640

DRAWING TITLE

RC DETAILS OF BASEMENT WALLS.

SHEET 2.

SCALES 1:50 & 1:25

--	--

CONTRACT No	DRG No
501180C	20-308