



NOTES

1. ALL MATERIALS AND WORKMANSHIP TO BE STRICTLY IN ACCORDANCE WITH THE SPECIFICATION AND ALL RELEVANT BRITISH STANDARDS.
2. ABBREVIATIONS  
B-BOTTOM T-TOP  
EF-EACH FACE NF-NEAR FACE FF-FAR FACE  
AB-ALTERNATE BARS  
ABS-ALTERNATE BARS STAGGERED  
ABR-ALTERNATE BARS REVERSED
3. ALL REINFORCEMENT TO BE HIGH YIELD TYPE B500A, B500B OR B500C RIBBED BARS TO BS4449:2005.
4. BENDING AND SCHEDULING OF REINFORCEMENT TO BE IN ACCORDANCE WITH BS 8666 : 2005
5. CONCRETE COVER TO REINFORCEMENT AS FOLLOWS:-  
FOR 300 THICK WALLS; 40mm. TO OUTSIDE FACE & 25mm. TO INSIDE FACE  
FOR 200 THICK WALLS; 40mm. TO OUTSIDE FACE & 25mm. TO INSIDE FACE  
FOR 150 THICK WALLS; 25mm. TO OUTSIDE FACE & 25mm. TO INSIDE FACE  
40mm. COVER TO ALL OTHER FACES IE. TOP OF WALL & LEDGES ETC.
6. REINFORCEMENT DETAILED ON THIS DRAWING IS SCHEDULED ON BAR LISTS Nos 312/1,2 & 3.
7. THIS DRAWING TO BE READ IN CONJUNCTION WITH RELEVANT ARCHITECTS DRAWINGS & SEJC DETAILS.
8. ALL KICKERS FORMED AT THE DISCRETION OF THE CONTRACTOR (ASSUMED 150mm. HIGH, FOR DETAILING PURPOSES)

MK	REVISIONS	BY	DATE	CHK

STATUS:-  
AS-BUILT

DRAWN BY -- SH.      DATE -- MAY '07  
CHECKED BY --      DATE --  
PROJECT ENGINEER --      DATE --

CLIENT.

**CTP'S JAMES**

ARCHITECT.  
**FaulknerBrowns**

CONTRACT  
**WAKEFIELD WATERFRONT  
PHASE 1,  
BUILDING 20**

**SEJC Consulting Engineers**  
Consulting Structural & Civil Engineers

Sanderson House, Station Road, Horforth, Leeds LS18 5NT  
Telephone 0113 2590090 Fax 0113 2599640

DRAWING TITLE  
**RC DETAILS OF  
BASEMENT WALLS.**

SHEET 5.

SCALES 1:50 & 1:25

CONTRACT No	DRG No
501180C	20-312